

Status of the LHC and the future of



a politically incorrect title...

Annual Theory Meeting, Durham

J. Engelen

December 20, 2005



Contents



- Status Large Hadron Collider project
 - Accelerator / Collider
 - Experiments
 - Computing
- Physics prospects
- Beyond LHC
 - CLIC or ILC (exclusive 'or')
 - Thoughts on Proton Accelerators for the Future (PAF) and Physics Opportunities (POFPA)
 - The future of CERN



The Large Hadron Collider

The Large Hadron Collider: 14 TeV pp collisions at $10^{34} \text{ cm}^{-2}\text{s}^{-1}$

New energy domain (x10), new luminosity domain (x100)


Will have to cross threshold of electroweak symmetry breaking; unitarity of WW scattering requires $M_{\text{Higgs}} < 850 \text{ GeV}$

Many possibilities: Standard Higgs – SUSY (many possibilities...)
–Large Extra Dimensions (quantum gravity)

–and many more results on CP violation, Quark Gluon Plasma, QCD, ..., surprises...

The LHC results will determine the future course of High Energy Physics

CERN: the World's Most Complete Accelerator Complex (not to scale)




- | | | | |
|------------|---------------|------------------------------|--------------------------------|
| ▶ protons | ▶ antiprotons | AD Antiproton Decelerator | LHC Large Hadron Collider |
| ▶ ions | ▶ electrons | PS Proton Synchrotron | n-ToF Neutron Time of Flight |
| ▶ neutrons | ▶ neutrinos | SPS Super Proton Synchrotron | CNGS CERN Neutrinos Gran Sasso |
| | | | CTF3 CLIC Test Facility 3 |

Project leader: Lyndon Evans

LHC Status




Superconducting cable 1 (dipole inner layer)



416th and last BNN dipole (November 2005)



Cryodipole overview



Preparation for installation in SMI2



Hall SMI2



First cryodipole lowered on 7 March 2005




Transport in the
tunnel is very
tight!



Transfer on jacks



Cryomagnets interconnect in the tunnel




Electrical quality control in the tunnel






Cryogenics overview



Staged commissioning plan for protons



- I. **Pilot physics run**
 - First collisions
 - 43 bunches, no crossing angle, no squeeze, moderate intensities
 - Push performance (156 bunches, partial squeeze in 1 and 5, push intensity)
 - Performance limit $10^{32} \text{ cm}^{-2} \text{ s}^{-1}$ (event pileup)
- II. **75ns operation**
 - Establish multi-bunch operation, moderate intensities
 - Relaxed machine parameters (squeeze and crossing angle)
 - Push squeeze and crossing angle
 - Performance limit $10^{33} \text{ cm}^{-2} \text{ s}^{-1}$ (event pileup)
- III. **25ns operation I**
 - Nominal crossing angle
 - Push squeeze
 - Increase intensity to 50% nominal
 - Performance limit $2 \cdot 10^{33} \text{ cm}^{-2} \text{ s}^{-1}$
- IV. **25ns operation II**
 - Push towards nominal performance

Stage I physics run

$$L = \frac{N^2 k_b f \gamma}{4\pi \epsilon_n \beta^*} F$$

$$\text{Eventrate / Cross} = \frac{L \sigma_{TOT}}{k_b f}$$

- Start as simple as possible
- Change 1 parameter (k_b N $\beta^*_{1,5}$) at a time
- All values for
 - nominal emittance
 - 7TeV
 - 10m β^* in point 2 (luminosity looks fine)

Protons/beam $\leq 10^{13}$
(LEP beam currents)

Stored energy/beam ≤ 10 MJ
(SPS fixed target beam)

Parameters			Beam levels		Rates in 1 and 5		Rates in 2	
k_b	N	$\beta^*_{1,5}$ (m)	I_{beam} proton	E_{beam} (MJ)	Luminosity ($\text{cm}^{-2}\text{s}^{-1}$)	Events/ crossing	Luminosity ($\text{cm}^{-2}\text{s}^{-1}$)	Events/ crossing
1	10^{10}	18	$1 \cdot 10^{10}$	10^{-2}	10^{27}	$\ll 1$	$1.8 \cdot 10^{27}$	$\ll 1$
43	10^{10}	18	$4.3 \cdot 10^{11}$	0.5	$4.2 \cdot 10^{28}$	$\ll 1$	$7.7 \cdot 10^{27}$	$\ll 1$
43	$4 \cdot 10^{10}$	18	$1.7 \cdot 10^{12}$	2	$6.8 \cdot 10^{29}$	$\ll 1$	$1.2 \cdot 10^{30}$	0.15
43	$4 \cdot 10^{10}$	2	$1.7 \cdot 10^{12}$	2	$6.1 \cdot 10^{30}$	0.76	$1.2 \cdot 10^{30}$	0.15
156	$4 \cdot 10^{10}$	2	$6.2 \cdot 10^{12}$	7	$2.2 \cdot 10^{31}$	0.76	$4.4 \cdot 10^{30}$	0.15
156	$9 \cdot 10^{10}$	2	$1.4 \cdot 10^{13}$	16	$1.1 \cdot 10^{32}$	3.9	$2.2 \cdot 10^{31}$	0.77

Stage II physics run

- Relaxed crossing angle (250 μ rad)
- Start un-squeezed
- Then go to where we were in stage I
- All values for
 - nominal emittance
 - 7TeV
 - 10m β^* in points 2 and 8

$$L = \frac{N^2 k_b f \gamma}{4\pi \epsilon_n \beta^*} F$$

$$F = 1 / \sqrt{1 + \left(\frac{\theta_c \sigma_z}{2\sigma^*}\right)^2}$$

$$\text{Event rate / Cross} = \frac{L \sigma_{TOT}}{k_b f}$$

Protons/beam \approx few 10^{13}

Stored energy/beam \lesssim 100MJ

Parameters			Beam levels		Rates in 1 and 5		Rates in 2 and 8	
k_b	N	β^* 1,5 (m)	I_{beam} proton	E_{beam} (MJ)	Luminosity (cm ⁻² s ⁻¹)	Events/crossing	Luminosity (cm ⁻² s ⁻¹)	Events/crossing
936	4 10^{10}	18	3.7 10^{13}	42	1.5 10^{31}	\ll 1	2.6 10^{31}	0.15
936	4 10^{10}	2	3.7 10^{13}	42	1.3 10^{32}	0.73	2.6 10^{31}	0.15
936	4 10^{10}	1	3.7 10^{13}	42	2.5 10^{32}	1.4	2.6 10^{31}	0.15
936	9 10^{10}	1	8.4 10^{13}	94	1.2 10^{33}	7	1.3 10^{32}	0.76

Stage III physics run

- Nominal crossing angle (285 μrad)
- Start un-squeezed
- Then go to where we were in stage II
- All values for
 - nominal emittance
 - 7TeV
 - 10m β^* in points 2 and 8

$$L = \frac{N^2 k_b f \gamma}{4\pi \epsilon_n \beta^*} F$$

$$F = 1 / \sqrt{1 + \left(\frac{\theta_c \sigma_x}{2\sigma^*}\right)^2}$$

$$\text{Eventrate / Cross} = \frac{L \sigma_{\text{TOT}}}{k_b f}$$

Protons/beam $\approx 10^{14}$

Stored energy/beam $\approx 100\text{MJ}$

Parameters			Beam levels		Rates in 1 and 5		Rates in 2 and 8	
k_b	N	$\beta^* 1,5$ (m)	I_{beam} proton	E_{beam} (MJ)	Luminosity ($\text{cm}^{-2}\text{s}^{-1}$)	Events/ crossing	Luminosity ($\text{cm}^{-2}\text{s}^{-1}$)	Events/ crossing
2808	$4 \cdot 10^{10}$	18	$1.1 \cdot 10^{14}$	126	$4.4 \cdot 10^{31}$	$\ll 1$	$7.9 \cdot 10^{31}$	0.15
2808	$4 \cdot 10^{10}$	2	$1.1 \cdot 10^{14}$	126	$3.8 \cdot 10^{32}$	0.72	$7.9 \cdot 10^{31}$	0.15
2808	$5 \cdot 10^{10}$	2	$1.4 \cdot 10^{14}$	157	$5.9 \cdot 10^{32}$	1.1	$1.2 \cdot 10^{32}$	0.24
2808	$5 \cdot 10^{10}$	1	$1.4 \cdot 10^{14}$	157	$1.1 \cdot 10^{33}$	2.1	$1.2 \cdot 10^{32}$	0.24
2808	$5 \cdot 10^{10}$	0.55	$1.4 \cdot 10^{14}$	157	$1.9 \cdot 10^{33}$	3.6	$1.2 \cdot 10^{32}$	0.24
Nominal			$3.2 \cdot 10^{14}$	362	10^{34}	19	$6.5 \cdot 10^{32}$	1.2

Conclusions Status LHC



- All key objectives have been reached for the end of 2005.
 - End of repair of QRL, reinstallation of sector 7-8 and cold test of sub-sectors A and B.
 - Cool-down of full sector 8-1.
 - Pressure test of sector 4-5.
 - Endurance test of full octant of power converters.
- Magnet installation rate is now close to 20/week, with more than 200 installed. This, together with interconnect work, will remain the main bottleneck until the end of installation.

The Detectors




Event rate 20 – 25 per bunch crossing (every 25 ns)
--> 10^9 events / s --> 10^{11} – 10^{12} tracks / s

Very remarkable: experiments will, in this environment:

- reconstruct secondary vertices from B mesons, only mm's away from the primary vertex.
- reconstruct individual photons with sufficient energy and angular resolution for (light) Higgs detection

in addition to many more capabilities: they are 'general purpose – 4π ' detectors, featuring tracking, magnetic momentum analysis, calorimetry, muon spectrometry, in an almost hermetic setup

ATLAS (spokesperson Peter Jenni)



ATLAS superimposed to the 5 floors of building 40




<i>Diameter</i>	<i>25 m</i>
<i>Barrel toroid length</i>	<i>26 m</i>
<i>End-cap end-wall chamber span</i>	<i>46 m</i>
<i>Overall weight</i>	<i>7000 Tons</i>

The Barrel Toroid



ANSYS



- 20 m diam. x 25 m length
- 8200 m³ volume
- 170 t superconductor
- 700 t cold mass
- 1320 t total weight
- 90 km superconductor
- 20.5 kA at 4.1 T
- 1.55 GJ stored Energy

8 coils interconnected
with an aluminum warm
structure

BT Mechanical Assembly




- ◆ Difficult but safe manipulations
- ◆ Use of 2 lifting frames
- ◆ Hydraulic winch with load capacity 190T (subcontracted)






Barrel Toroid installation status

The mechanical installation is complete, electrical and cryogenic connections are being made now, for a first in-situ cool-down and **excitation test in spring 2006**






End-Cap Toroids

The picture shows a successful trial assembly of the full cold mass in front of the vacuum vessel for the first ECT (side A)

The final assembly is planned to be completed in the coming weeks



Inner Detector (ID)





The Inner Detector (ID) is organized into four sub-systems:

Pixels ($0.8 \cdot 10^8$ channels)

Silicon Tracker (SCT)
($6 \cdot 10^6$ channels)

Transition Radiation
Tracker (TRT)
($4 \cdot 10^5$ channels)





Pixels



Recent technical problem



- Corrosion leaks in the barrel cooling tubes (highest priority is given to implement an optimum strategy for repair and rebuilding of staves)

This means that there is a schedule risk for the installation of a 3-layer system in time for the start-up, even though the recovery progress is good

The installation schedule has been adapted to accommodate a late availability

(Note that the Pixel sub-system can be installed independently from the rest of the Inner Detector)

Example of a galvanic corrosion hole that is opening





Completed barrel stave



Silicon Tracker (SCT)



All four barrel cylinders are complete and at CERN



Assembly of the four barrel cylinders is complete (left), and the SCT barrel is now being prepared for insertion into the TRT barrel




Transition Radiation Tracker (TRT)



The module construction for the end-cap TRT will also be complete by the end of the year, and the first end-cap side (A and B wheels) has been assembled and integrated, whereas the barrel has been ready since several months


A previously reported excessive failure rate of HV fuses has been overcome

A new technical issue concerns leaks in the barrel cooling line manifolds, due to bad brazing → a redesign was adopted in a recent review and will be implemented in the coming months




The first of the two end-cap TRTs (A and B type wheels) fully assembled


LAr and Tile Calorimeters



Barrel LAr and Tile Calorimeters



A cosmic muon registered in the barrel Tile calorimeter



The barrel LAr and Tile calorimeters have been since some time in the cavern in their 'garage position' to be moved into their final position at the end of this month



The delicate transport of the first LAr End-Cap to point-1 (22nd Sep)

The lower part of the Extended Barrel Tile Calorimeter and the LAr End-Cap are ready for the lowering into the cavern (side C)




LAr and Tile Calorimeter End-Caps


Next major activities:

End-Cap C installation
from Nov 05 → Jan 06

End-Cap A installation
from Jan 06 → Mar 06



Muon Spectrometer Instrumentation



The Muon Spectrometer is instrumented with precision chambers and fast trigger chambers

A crucial component to reach the required accuracy is the sophisticated alignment measurement and monitoring system

Precision chambers:

- MDTs in the barrel and end-caps
- CSCs at large rapidity for the innermost end-cap stations

Trigger chambers:

- RPCs in the barrel
- TGCs in the end-caps



At the end of this year the huge and long effort of series chamber production in many sites will be completed for all chamber types



Barrel Muon MDTs



MDT Chamber Production (w/o EE)




A major effort is spent in the preparation and testing of the barrel muon stations (MDTs and RPCs for the middle and outer stations) before their installation in-situ

The electronics and alignment system fabrications for all MDTs are on schedule

Installation of barrel muon station



Summary representation of the installation activities in the experimental cavern at Point-1 (Installation Schedule Version 7.09)





The CMS Detector

Spokesperson: M. Della Negra

CALORIMETERS


Scintillating
PbWO4 crystals

ECAL

HCAL

Plastic scintillator/brass
sandwich

SUPERCONDUCTING COIL



IRON YOKE

TRACKER

Silicon Microstrips
Pixels

Total weight : 12,500 t
Overall diameter : 15 m
Overall length : 21.6 m
Magnetic field : 4 Tesla

MUON ENDCAPS

MUON BARREL

Drift Tube
Chambers

Resistive Plate
Chambers

Cathode Strip Chambers
Resistive Plate Chambers


Coil Swiveling and Insertion



Swiveling of coil carried out on 25 Aug.



Coil inserted 14 Sep.




Platform disconnected from Coil (28 Sep)




Swivelling of inner vac tank: ~ 20 Oct
Coil cool-down and start of electrical tests : Jan 06

Inner Tracker




Tracker Outer Barrel

The TOB Support Structure partially inserted
into the Tracker Support Tube






The Trial Insertion of
Two RODs into the TOB Structure


Electromagnetic CALorimeter




Barrel Muons: DriftTubes Assembly and Installation



**Barrel Yoke wheels YB+2 and YB+1:
80 (out of 210) DT/RPC Ch. Installed; 40 Ch. commissioned**



Cosmic Muons in CMS





Data path

phi theta C:\Documents and Settings\masetti\Desktop\Test_MC\my\ New event Stop Event number 448 printing




MB1

MB2

MB3

MB4

Endcap Muons: ME2, ME3 and ME4 stations



CMS Schedule



Currently see a delay of an average of 6 weeks wrt v34.2. Will try to regain time during repetitive operations after lowering in second half of 2006.

	v34.2	Estimate
• Magnet test on surface start	Nov 05	Feb 06
• Start Lowering CMS (HF first)	Feb 06	Apr 06
• ECAL barrel EB+ installation	Mar 06	May 06
• ECAL: EB- installation & cabling	Oct 06	Oct 06
• Tracker installation + cabling start	Nov 06	Nov 06
• Beampipe Installation	Mar-Apr 07	Mar-Apr 07
• CMS “ready to close” for beam	15 Jun 07	15 Jun 07
• CMS “ready for beam”	30 Jun 07	30 Jun 07

During first shutdown after pilot physics run:


• Pixel Tracker installation	Dec 07	Dec 07
• EE/ES installation	Dec07/Feb 08	Dec07/Feb

LHCb Spectrometer

(spokesman Tatsuya Nakada)



$gg \rightarrow b \bar{b}$



Beam Pipe



- 25 mrad Be section completed
- 10 mrad Be
1st section being tested at IHEP, Protvino
- 10 mrad Be
2nd section under construction by Kompozit, Moscow



- All the other components are also under construction


VERtex LOcator



VELO tank installed in the support frame and connected to the vacuum system



CO₂ cooling capillaries



r-sensor



hybrid and module support



feedthrough flanges

All the parts are now being produced

RICH-2 transport to IP8







L-1 and HLT hardware now completely unified



Old scheme



Newly adopted 1 MHz readout scheme



This was foreseen as an upgrade, but the cost of the network switches has dropped faster than anticipated.


LHCb



Production, installation and commissioning of all the subsystems are progressing well

No problem with the TT and ST sensor delivery any more

Still tight schedule for VELO sensors, RICH1 mechanics, HPD's and Muon chambers



ALICE Detector




(spokesman Juergen Schukraft)



Space Frame LOAD TEST



ITS mechanics being assembled



TPC ROC Installation



More experiments at LHC




Totem: elastic and total cross section;
hard diffraction (together with CMS)

Moedal: magnetic monopoles

LHCf: very forward production of π^0 's, γ 's (cf. energy
calibration of very high energy cosmic rays)

Computing



The LHC Computing Grid: LCG


(Project leader Les Robertson)



is about storing 15 PB (imagine!) of new data per year; processing them and making the information available to thousands of physicists all around the world!

Model: 'Tiered' architecture; 100,000 processors; multi-PB disk, tape capacity

Leading 'computing centers' involved



Any Tier-2 may access data at any Tier-1

T2s and T1s are inter-connected by the general purpose research networks

Dedicated 10 Gbit links



Brookhaven

IN2P3

GridKa

TRIUMF

ASCC

Fermilab

Nordic

CNAF

SARA

NIKHEF

PIC

RAL

T2

T2

T2

T2

T2

T2

T2

T2

T2

T2

T2

T2


T2

T2

T2

T2

Building the Service




LCG



- The "Baseline Services" for the LCG services at startup have been agreed. These are the basic services that must be provided at CERN, Tier-1 and Tier-2 centres, and have to be in operation for Service Challenge 4 in April 2006.
- A detailed plan for Service Challenge 3 has been agreed with Tier-1 sites and the experiments. Service Challenge 3 is being prepared now and is scheduled to open as a stable service including 9 Tier-1 centres and several Tier-2s in September 2005.
- The deployment plan for the new CASTOR mass storage management system at CERN has been agreed with the experiments, with the aim of completing the migration of LHC to this system by the end of February 2006.
- The TDR for the initial LHC computing services is complete.

The LCG project is taking an active part in the preparation of the proposal for the second phase of the EGEE project (April 2006-March 2008). This will be an evolution of the current project, with the major emphasis remaining grid operations.

Physics



EXAMPLE of initial physics study




Studies of W and Z production

Constraints on Parton Distribution Functions (PDF) from W and Z rapidity distributions

Simulation of realistic experimental conditions for $W \rightarrow e\nu$:

- Backgrounds
- Systematics on charge misidentification (Rome data)



PDF constraining potential of ATLAS: Include 1M ATLAS pseudo-data (ATLFAST) in ZEUS PDF fit

Impose a 4% uncertainty on data points

Observe 35% error reduction on low- x gluon shape parameter λ ($xg(x) \sim x^{-\lambda}$)

EXAMPLE, TOP STUDIES



no b-tagging required,
straightfwd analysis

Missing $E_T > 20 \text{ GeV}$
 1 lepton $P_T > 20 \text{ GeV}$
 4 jets(R=0.4) $P_T > 40 \text{ GeV}$



Assign jets to W, top decays

1 Hadronic top:

Three jets with highest vector-sum p_T as the decay products of the top

2 W boson:

Two jets in hadronic top with highest momentum in reconstructed jjj C.M. frame.



Which physics the first year(s) ?



Expected event rates at production in ATLAS or CMS at $L = 10^{33} \text{ cm}^{-2} \text{ s}^{-1}$


Process	Events/s	Events for 10 fb^{-1}	<u>Total statistics collected</u> at previous machines by 2007
$W \rightarrow e\nu$	15	10^8	10^4 LEP / 10^7 Tevatron
$Z \rightarrow ee$	1.5	10^7	10^7 LEP
$t \bar{t}$	1	10^7	10^4 Tevatron
$b \bar{b}$	10^6	$10^{12} - 10^{13}$	10^9 Belle/BaBar
$H \ m=130 \text{ GeV}$	0.02	10^5	?
gluino gluino $m=1 \text{ TeV}$	0.001	10^4	---
Black holes $m > 3 \text{ TeV}$ ($M_D=3 \text{ TeV}, n=4$)	0.0001	10^3	---

Already in first year, large statistics expected from:

- known SM processes \rightarrow understand detector and physics at $\sqrt{s} = 14 \text{ TeV}$
- several New Physics scenarios



Implications for light Higgs (assuming the same luminosity/detector/analysis)



	$qq \rightarrow WH \rightarrow \ell\nu bb$ $qq \rightarrow ZH \rightarrow \ell\ell bb$ $m_H = 120 \text{ GeV}$	$gg \rightarrow H \rightarrow WW$ $\rightarrow \ell\nu \ell\nu$ $m_H = 160 \text{ GeV}$
S(14)/S(2)	$\approx 5^*$	≈ 30
B(14)/B(2)	≈ 25	≈ 6
S/B(14)/S/B(2)	≈ 0.2	≈ 3
S/ $\sqrt{B(14)}$ / S/ $\sqrt{B(2)}$	≈ 1	≈ 7

* Acceptance ~ 2 times larger at Tevatron
(physics is more central, less initial-state g radiation)

EW cross-sections (e.g. $qq \rightarrow W, Z, WH$):



LHC/Tevatron ~ 10

QCD cross-sections (e.g. $t\bar{t}, gg \rightarrow H$):

LHC/Tevatron ≥ 100 (because of gluon PDF) \rightarrow cf HERA results

$$\left. \begin{array}{l} e/\text{jet} \sim 10^{-3} \\ e/\text{jet} \sim 10^{-5} \end{array} \right\} \begin{array}{l} \sqrt{s} = 2 \text{ TeV} \\ \sqrt{s} = 14 \text{ TeV} \end{array} \left. \vphantom{\begin{array}{l} e/\text{jet} \sim 10^{-3} \\ e/\text{jet} \sim 10^{-5} \end{array}} \right\} p_T > 20 \text{ GeV}$$

Standard Model Higgs



$m_H \sim 115 \text{ GeV}$ 10 fb^{-1}

total $S/\sqrt{B} \approx 4^{+2.2}_{-1.3}$

ATLAS	$H \rightarrow \gamma\gamma$	$ttH \rightarrow ttbb$	$qqH \rightarrow qq\tau\tau$ ($ll + \ell\text{-had}$)
S	130	15	~ 10
B	4300	45	~ 10
S/\sqrt{B}	2.0	2.2	~ 2.7

Full GEANT simulation, simple cut-based analyses

K-factor $\equiv \frac{\sigma_{\text{NLO}}}{\sigma_{\text{LO}}} \approx 2$ not included

Conclusions



The LHC project (machine; detectors; LCG) is well underway for physics in 2007

Detector construction is generally proceeding well, although not without concerns in some cases; an enormous integration/installation effort is ongoing – schedules are tight but are also taken very seriously.

LCG (like machine and detectors at a technological level that defines the new 'state of the art') needs to fully develop the functionality required; new 'paradigm'.

Large potential for exciting physics.

The Compact Linear Collider



CLIC aim:

*develop technology for e^-/e^+ collider with
 $E_{CMS} = 1 - 5 \text{ TeV}$*

Physics motivation:


*"Physics at the CLIC Multi-TeV Linear Collider :
report of the CLIC Physics Working Group,"
CERN report 2004-5*

Present mandate:

Demonstrate all key feasibility issues by 2010

BASIC FEATURES OF CLIC

High gradient **150 MV/m**




Overall layout of
CLIC for $E_{CMS} = 3 \text{ TeV}$

Two-Beam Acceleration Scheme

- “Compact” collider - overall length < 34 km
- Normal conducting accelerating structures
- High acceleration frequency (30 GHz)

- Capable to reach high frequency
- Cost-effective & efficient (~ 10% overall)
- Simple tunnel, no active elements
- “Modular” design, can be built in stages

A short history of CLIC



The CLIC Technology related key issues as identified by 2nd ILC-TRC, 2003



Covered by CTF3

R1: Feasibility

- R1.1: Test of damped accelerating structure at design gradient and pulse length
- R1.2: Validation of drive beam generation scheme with fully loaded linac operation
- R1.3: Design and test of damped ON/OFF power extraction structure

R2: Design finalization


- R2.1: Developments of structures with hard-breaking materials (W, Mo...)
- R2.2: Validation of stability and losses of DB decelerator; Design of machine protection system
- R2.3: Test of relevant linac sub-unit with beam
- R2.4: Validation of drive beam 40 MW, 937 MHz Multi-Beam Klystron with long RF pulse *
- R2.5: Effects of coherent synchrotron radiation in bunch compressors
- R2.6: Design of an extraction line for 3 TeV c.m.

Covered by EUROTeV

* Feasibility study done - need development by industry.

N.B.: Drive beam acc. structure parameters can be adapted to other klystron power levels

CTF3 layout





CTF3 schedule

	2004	2005	2006	2007	2008	2009
Drive Beam Accelerator	█					
30 GHz power test stand in Drive Beam accelerator	█	█				
30 GHz power testing (4 months per year)		█	█	█	█	
R1.1 feasibility test of CLIC structure					█	
Delay Loop	█	█				
Combiner Ring	█	█	█			
R1.2 feasibility test of Drive beam generation				█		
CLIC Experimental Area (CLEX)		█	█			
R1.3 feasibility test PETS				█		
Probe Beam			█	█		
R2.3 feasibility test representative CLIC linac section					█	
Test beam line		█	█	█	█	
R2.2 Beam stability bench mark tests					█	█

The future



CERN: prepare for important decisions in 2010.

Most important input: first LHC results

Also available: result of CLIC feasibility study; CTF3


And (?): strategy for neutrino oscillation studies

Etc. (smaller but important projects, e.g. $K \rightarrow \pi \nu \nu$)

In CERN's present Medium Term Plan (2005 + 5 years) there is only room for LHC (priority number 1, of course) and 'paying the debt' (reaching a maximum of 1 GSF...). The debt should be paid for by 2011 – but additional funding is required to prepare the decisions to be taken in 2010

- accelerator consolidation, construction and R&D (in addition to CLIC)
 - LINAC4 and beyond;
 - SPL; beta beams; neutrino factory design study (following scoping study)
- Detector R&D (LHC luminosity upgrade; ILC, CLIC; neutrino detectors)

Scenarios for proton injectors (1/4): - possible combinations



Scenarios for proton injectors (2/4):

- **PS+ based** (superconducting synchrotron 1.4 → ~ 50 GeV / 0.3 Hz)

		PS+ based		
	<i>Linac4</i> PSB PS SPS	<i>Linac4</i> PSB <i>PS+</i> SPS	<i>Linac4</i> <i>SPL</i> <i>PS+</i> SPS	<i>Linac4</i> <i>SPL</i> <i>PS+</i> <i>SPS+</i>
L1, L2	Ultimate beam from PS	PS replaced Ultimate beam from SPS	PSB & PS replaced Ultimate beam from SPS	PSB, PS & SPS replaced
SLHC	+	++	++	+++
DLHC	+	++	++	+++
β beam	-	-	++ ($\gamma > 100$)	++ ($\gamma > 200$)
ν Factory	-	-	+++ (~5 GeV prod. beam)	+++ (~5 GeV prod. beam)
K, μ	-	x00 kW beam at 50 GeV	x00 kW beam at 50 GeV	x00 kW beam at 50 GeV
Nuclear Physics	-	-	+++	+++

- CERN Council Strategy Group
- Special Council meeting in Lisbon, July 2006
- Later in 2006: Medium Term Plan that is not just an extrapolation of the previous one